

Recessed Mounted 4C Horizontal Mailboxes

RECESSED MOUNTED 4C HORIZONTAL MAILBOXES FRONT OR REAR LOADING




Made of heavy duty aluminum and stainless steel hardware, Salsbury 3700 series recessed mounted 4C horizontal mailboxes and parcel lockers are U.S.P.S. approved and are available with standard MB1 mailbox doors (12-3/4" W x 3-1/4" H). Larger MB2, MB3 and MB4 mailbox doors are available for custom units. All pre-numbered mailbox doors include a heavy duty cam lock with a dust/rain shield and three (3) keys. Recessed mounted 4C horizontal mailbox units include factory installed 1" W x 1/4" D trim and are available in configurations that are one door wide (single column) and two (2) doors wide (double column). The Salsbury maximum height units (3716D-15) have three (3) fully integrated parcel lockers (2 PL4.5 and 1PL5) and fifteen (15) standard MB1 mailbox doors and meet the U.S.P.S. 4C requirement of one parcel locker for every five (5) tenant compartments. Fully integrated and stand-alone parcel lockers are available in heights ranging from the equivalent of three (3) standard MB1 mailbox doors (PL3 - 10-1/4" high) to six (6) standard MB1 mailbox doors (PL6 - 20-3/4" high). Each unit includes a compartment for outgoing mail collection and is labeled "Outgoing Mail". The outgoing mail compartment includes a weather protection flap and a 11-3/4" W x 3/4" H mail slot. Designed for indoor or outdoor use, recessed mounted 4C horizontal mailboxes feature a durable powder coated finish available in four (4) contemporary colors.

4C

Note: Salsbury 3700 series recessed mounted 4C horizontal mailboxes and parcel lockers are U.S.P.S. approved and meet the specifications of USPS-STD-4C. These units are required for new construction and major renovations.

STANDARD FEATURES



Front view of 3716D-15 Front Loading Recessed Mounted Double Column Unit displayed



ALL ALUMINUM
CONSTRUCTION

#3716D-15 maximum height recessed mounted 4C horizontal mailboxes in aluminum finish with optional custom engraved placards (#3767) displayed

MAXIMUM HEIGHT UNITS - 57-1/8" H

11 DOOR HIGH UNITS - 41-3/8" H



3716D-20
Double Column - Front Loading



3716D-15
Double Column - Front Loading



3711D-20
Double Column - Front Loading




3711D-10
Double Column - Front Loading

RECESSED MOUNTED 4C HORIZONTAL MAILBOXES - FRONT OR REAR LOADING - U.S.P.S. APPROVED


MODEL	DESCRIPTION	UNIT SIZE - FL and RL (includes trim)	WEIGHT
MAXIMUM HEIGHT UNITS - 57-1/8" H (maximum allowable height)			
3716D-20 ^{1,2,3}	20 MB1 Doors and 2 Parcel Lockers (PL4.5's)	31-1/8" W x 57-1/8" H x 16-1/2" D	170 lbs.
3716D-15 ^{1,2,3}	15 MB1 Doors and 3 Parcel Lockers (PL4.5's, PL5)	31-1/8" W x 57-1/8" H x 16-1/2" D	160 lbs.
3716D-10 ^{1,2,3}	10 MB1 Doors and 4 Parcel Lockers (PL4.5's, PL5's)	31-1/8" W x 57-1/8" H x 16-1/2" D	150 lbs.
3716D-6P ^{1,2,3}	6 Parcel Lockers (PL4.5's, PL5's, PL6's)	31-1/8" W x 57-1/8" H x 16-1/2" D	145 lbs.
3716S-09 ^{1,2,3}	9 MB1 Doors and 1 Parcel Locker (PL4.5)	17" W x 57-1/8" H x 16-1/2" D	85 lbs.
3716S-06 ^{1,2,3}	6 MB1 Doors and 2 Parcel Lockers (PL3, PL4.5)	17" W x 57-1/8" H x 16-1/2" D	85 lbs.
3716S-3P ^{1,2,3}	3 Parcel Lockers (PL4.5, PL5, PL6)	17" W x 57-1/8" H x 16-1/2" D	80 lbs.

MODEL	DESCRIPTION	UNIT SIZE - FL and RL (includes trim)	WEIGHT
11 DOOR HIGH UNITS - 41-3/8" H (equivalent to 11 standard mailbox doors (MB1) high)			
3711D-20 ^{1,2,3}	20 MB1 Doors - no Parcel Lockers	31-1/8" W x 41-3/8" H x 16-1/2" D	145 lbs.
3711D-15 ^{1,2,3}	15 MB1 Doors and 1 Parcel Locker (PL5)	31-1/8" W x 41-3/8" H x 16-1/2" D	135 lbs.
3711D-10 ^{1,2,3}	10 MB1 Doors and 2 Parcel Lockers (PL5's)	31-1/8" W x 41-3/8" H x 16-1/2" D	135 lbs.
3711D-4P ^{1,2,3}	4 Parcel Lockers (PL5's, PL6's)	31-1/8" W x 41-3/8" H x 16-1/2" D	130 lbs.
3711S-09 ^{1,2,3}	9 MB1 Doors - no Parcel Lockers	17" W x 41-3/8" H x 16-1/2" D	75 lbs.
3711S-04 ^{1,2,3}	4 MB1 Doors and 1 Parcel Locker (PL5)	17" W x 41-3/8" H x 16-1/2" D	75 lbs.
3711S-2P ^{1,2,3}	2 Parcel Lockers (PL5, PL6)	17" W x 41-3/8" H x 16-1/2" D	65 lbs.

MAXIMUM HEIGHT UNITS - 57-1/8" H



11 DOOR HIGH UNITS - 41-3/8" H



Additional Units and Volume Discount Pricing Available at Mailboxes.com!

¹ Specify

aluminum	bronze	sandstone	black

² Specify - front loading (FL) or rear loading (RL)

³ Specify - U.S.P.S. access or private access (order #3775 master commercial lock for private access on FL units and PL's)

Recessed Mounted 4C Horizontal Mailboxes

ARCHITECTURAL RESOURCES ONLINE

visit: www.mailboxes.com/Architectural-Resources

- Product Information
- 3D Revit / BIM Models
- Detailed Specifications
- Technical Drawings
- Installation Instructions
- AutoCAD Drawings
- Color Chart
- ADA Compliant Units Available 


- visit: www.mailboxes.com/ADA-4C-Mailboxes



4C

Note: Salsbury 3700 series recessed mounted 4C horizontal mailboxes and parcel lockers are U.S.P.S. approved and meet the specifications of USPS-STD-4C. These units are required for new construction and major renovations.

4C MAILBOX CONFIGURATOR




Access our 4C Configurator at:
www.mailboxes.com/4C-Configurator

Our 4C mailbox configurator will assist in determining the ideal combination of mailboxes and parcel lockers based on your specific requirements. This robust tool also allows you to customize 4C mailbox units and add numbering sequences to drawings. In addition to clear and easy to read elevation line drawings with dimensions, our online mailbox configurator will also provide you with PDF, Word, Excel and AutoCAD drawing files to download for your project. Purchasing products and requesting a quote online is simple and convenient.

4C CONNECTOR KIT

Made of heavy duty aluminum, 4C horizontal mailbox connector kits easily connect multiple recessed mounted mailbox units providing easy installation. Each standard and custom recessed mounted 4C horizontal mailbox unit includes one mailbox connector kit (hardware included).

Models displayed:
(2) 3716D-20 Front Loading Units
(1) 3716CK Connector Kit



4C horizontal mailbox connector kits connect recessed mounted units side by side and eliminate the need for wood studs between the units.

Note: For installations accessed by the U.S. Postal Service, the tenant locks in the top row of mailboxes must be no more than 67" above the finished floor and the bottom shelf of the lowest row of mailboxes must be no less than 28" above the finished floor. The U.S.P.S. master arrow lock must be a minimum of 36" and a maximum of 48" above the finished floor. The bottom shelf of parcel lockers must be at least 15" above the finished floor.

#3710D-10 recessed mounted
4C horizontal mailboxes in
bronze finish with optional custom
engraved placards (#3767) displayed

10 DOOR HIGH UNITS* - 37-7/8" H

6 DOOR HIGH UNITS* - 23-7/8" H



3710D-10

Double Column - Front Loading



3710S-04

Single Column - Front Loading



3706D-10

Double Column - Front Loading



3706S-04

Single Column - Front Loading



*All units meet ADA reach requirements when installed with the tenant locks in the top row of mailboxes no more than 48" above the finished floor and the bottom shelf of the lowest row of mailboxes no less than 28" above the finished floor.


RECESSED MOUNTED 4C HORIZONTAL MAILBOXES - FRONT OR REAR LOADING - U.S.P.S. APPROVED

MODEL	DESCRIPTION	UNIT SIZE - FL and RL (includes trim)	WEIGHT
-------	-------------	---------------------------------------	--------

10 DOOR HIGH UNITS - 37-7/8" H (equivalent to 10 standard mailbox doors (MB1) high)

3710D-10 ^{1,2,3}	10 MB1 Doors and 2 Parcel Lockers (PL4, PL4.5)	31-1/8" W x 37-7/8" H x 16-1/2" D	130 lbs.
3710D-09 ^{1,2,3}	9 MB1 Doors and 2 Parcel Lockers (PL4.5, PL5)	31-1/8" W x 37-7/8" H x 16-1/2" D	130 lbs.
3710D-06 ^{1,2,3}	6 MB1 Doors and 2 Parcel Lockers (PL6's)	31-1/8" W x 37-7/8" H x 16-1/2" D	125 lbs.
3710D-4P ^{1,2,3}	4 Parcel Lockers (PL5's)	31-1/8" W x 37-7/8" H x 16-1/2" D	120 lbs.
3710S-04 ^{1,2,3}	4 MB1 Doors and 1 Parcel Locker (PL4.5)	17" W x 37-7/8" H x 16-1/2" D	75 lbs.
3710S-03 ^{1,2,3}	3 MB1 Doors and 1 Parcel Locker (PL5)	17" W x 37-7/8" H x 16-1/2" D	70 lbs.
3710S-2P ^{1,2,3}	2 Parcel Lockers (PL5's)	17" W x 37-7/8" H x 16-1/2" D	65 lbs.

10 DOOR HIGH UNITS - 37-7/8" H




MODEL	DESCRIPTION	UNIT SIZE - FL and RL (includes trim)	WEIGHT
-------	-------------	---------------------------------------	--------

6 DOOR HIGH UNITS - 23-7/8" H (equivalent to 6 standard mailbox doors (MB1) high)

3706D-10 ^{1,2,3}	10 MB1 Doors - no Parcel Lockers	31-1/8" W x 23-7/8" H x 16-1/2" D	90 lbs.
3706D-09 ^{1,2,3}	9 MB1 Doors - no Parcel Lockers	31-1/8" W x 23-7/8" H x 16-1/2" D	90 lbs.
3706D-05 ^{1,2,3}	5 MB1 Doors and 1 Parcel Locker (PL5)	31-1/8" W x 23-7/8" H x 16-1/2" D	85 lbs.
3706D-2P ^{1,2,3}	2 Parcel Lockers (PL6's)	31-1/8" W x 23-7/8" H x 16-1/2" D	80 lbs.
3706S-04 ^{1,2,3}	4 MB1 Doors - no Parcel Lockers	17" W x 23-7/8" H x 16-1/2" D	50 lbs.
3706S-03 ^{1,2,3}	3 MB1 Doors - no Parcel Lockers	17" W x 23-7/8" H x 16-1/2" D	50 lbs.
3706S-1P ^{1,2,3}	1 Parcel Locker (PL6)	17" W x 23-7/8" H x 16-1/2" D	45 lbs.

6 DOOR HIGH UNITS - 23-7/8" H



Additional Units and Volume Discount Pricing Available at Mailboxes.com!

1 Specify



aluminum



bronze



sandstone



black

2 Specify - front loading (FL) or rear loading (RL)

3 Specify - U.S.P.S. access or private access (order #3775 master commercial lock for private access on FL units and PL's)



OUTGOING MAIL COMPARTMENT

Note: Recessed mounted 4C horizontal mailboxes include a compartment for outgoing mail collection that is labeled "Outgoing Mail".

4C Horizontal Mailbox Specifications & Options

- Manufactured by Salsbury Industries to USPS-STD-4C Specifications
 - Required for New Construction and Major Renovations
 - For Indoor or Outdoor Use
 - Fully Integrated or Stand-Alone Parcel Lockers
 - ADA Compliant Units Available 
- visit: www.mailboxes.com/ADA-4C-Mailboxes



Volume Discount Pricing Available at Mailboxes.com!

If Rear Loading: The front of the outgoing mail compartment is comprised of fixed panels (no access door). The rear of the unit incorporates one or two (2) access door(s) with heavy duty latches and continuous hinges. Units are available without rear access doors upon request. Note: Rear loading access is only available for recessed mounted units.



Front view of Rear Loading Recessed Mounted Double Column Unit displayed



Rear view of Rear Loading Recessed Mounted Unit with Rear Access Doors displayed

Note: U.S.P.S. standard 4C requires a minimum of one parcel locker for every five (5) tenant compartments. Parcel lockers are not required for installation sites with less than five (5) tenant compartments.



Custom recessed mounted 4C horizontal mailboxes in sandstone finish with optional custom engraved doors -black filled (#3774) displayed

DESIGN ASSISTANCE

Our design engineers are available to architects, specification writers and individuals involved in the design of mail distribution facilities, apartment complexes and commercial buildings. Visit the informative Architect Resources section of our website at: www.mailboxes.com/Architectural-Resources to download specifications, technical drawings, AutoCAD and BIM/Revit models. You can also submit required layout and options for a price quotation.

4C CONFIGURATOR


Access our 4C Configurator online at: www.mailboxes.com/4C-Configurator to customize units or submit your required layout for a price quotation online at www.mailboxes.com or to quotes@mailboxes.com.



If Front Loading: Units include one or two (2) master door(s) that swing(s) on continuous integral hinges. The outgoing mail compartment includes the access door and cannot be used for mail distribution. The rear of the unit incorporates a solid rear cover.



Note: Salsbury 4C horizontal mailboxes and parcel lockers are U.S.P.S. approved and meet the specifications of USPS-STD-4C. These units are required for new construction and major renovations.



Front view of Front Loading Recessed Mounted Double Column Unit displayed




Front view of Front Loading Recessed Mounted Double Column Unit with Doors Open displayed

4C HORIZONTAL MAILBOX SPECIFICATIONS & OPTIONS

FOR RECESSED MOUNTED, SURFACE MOUNTED AND FREE-STANDING MAILBOX UNITS

MAILBOX DOOR SIZES


Each aluminum door includes a heavy duty five (5) pin cylinder cam lock with a dust/rain shield and three (3) keys.



#3751¹ Replacement MB1 door and lock



#3752¹ Replacement MB2 door and lock



#3753¹ Replacement MB3 door and lock



#3754¹ Replacement MB4 door and lock

PARCEL LOCKER DOOR SIZES


Parcel lockers offer tenants a convenient way to receive packages on site and are fit with a two (2) key security system.



#3753P¹ Replacement PL3 door and lock



#3754P¹ Replacement PL4 door and lock



#3754.5P¹ Replacement PL4.5 door and lock



#3755P¹ Replacement PL5 door and lock



#3756P¹ Replacement PL6 door and lock

¹ Specify



FINISHES

The durable and corrosion resistant 4C units feature a durable powder coated finish available in aluminum, bronze, sandstone or black. Custom finishes (#3766) are available as an option upon request – minimum order of (100) doors.

DOOR IDENTIFICATION

Each standard 4C horizontal mailbox door has a 1" high number. The outgoing mail compartment is labeled "Outgoing Mail" and the parcel locker(s) are labeled with a "1P", "2P", etc. Custom identification systems are available as an option upon request.

CUSTOM ENGRAVED PLACARDS

1-3/4" W x 1-1/2" H custom engraved self-adhesive placards are available as an option upon request. (#3767)



#3767

OUTGOING MAIL COMPARTMENTS

One compartment in each unit is labeled "Outgoing Mail" and includes a weather protection flap and a 11-3/4" W x 3/4" H mail slot.

LOCKS

Each 4C mailbox door includes a heavy duty five (5) pin cylinder cam lock with a dust/rain shield and three (3) keys (2,000 different key changes). (#3790-5 - set of (5) #3790 locks)




#3790

- Additional keys per lock when ordering (#3798)
- Key blanks - box of (50) (#3799)
- Custom lock installation - cylinders provided by owner (for installations not serviced by the U.S.P.S.) (100 door minimum) (#3793)

For installations NOT serviced by the U.S.P.S.

- Mail slots (#3769)
- Standard slot size: 10-3/4" W x 3/4" H
- Custom slot sizes are available upon request.
- Plexiglass window 1-1/8" W x 7/8"H (#3771)
- Outgoing mail slot plug kit (#3770)



#3769



#3771

CUSTOM ENGRAVED DOORS

- Custom engraved door – regular (#3768)
- Custom engraved door – black filled (#3774)




#3768



#3774

MASTER COMMERCIAL LOCK


Factory installed if for private access - for front loading mailboxes and parcel lockers - with (2) keys (#3775)



#3775

TENANT PARCEL LOCKER LOCK


For parcel locker door - with (3) keys (#3776)



#3776

COMBINATION LOCK

Three (3) digit single dial combination lock with spring latch and automatic throw-off (for installations not serviced by the U.S.P.S.). Combination numbers can be changed by owner. (#3786)



#3786